Abstract estimate for improvements to old filter-beds for use as settling tanks and constructing a mixing channel at Chikmagalur.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
	I. Settling Tanks.				
1	Clearing jungle and removing debris to form site ...	L. S.			
2	Dismantling old brick masonry	C.ft.		525	
3	Cutting and removing old plaster and raking joints of old concrete bed and flooring of tanks ...	Sqr.		63.67	
4	Clearing sand or earth mounds in lower units and removing to form ramp all round	C.yds.		284	
5	Earthwork forming ramp alround including watering and tamping complete	"		298	
6	Grouting old flooring with neat cement mortar (1 : 2)	Sqr.		63.67	
7	Laying one course of brick on edge in (1 : 4) cement mortar complete with bonds as per design ...	Sqr.		63.67	
8	Laying 2½" thick cement concrete (1 : 2 : 4) over brick flooring	"		63.67	
9	Rounding steps in walls and tops of buttresses, with burnt stone jelly in cement mortar 1 : 4 and laying etc., complete	R.ft.		478	
10	Removing old plaster and raking joints of walls for new plastering	Sqr.		52.11	
11	Burnt brick in cement mortar (1 : 4) masonry for walls	C.ft.		3,981	
12	Providing and casting cement concrete (1 : 3 : 6) coping slabs over walls complete with plastering and smooth finishing	C.ft.		393	
13	Cement mortar plastering with "pudlo" waterproof compound ½" thick (1 : 3) proportion complete for flooring and walls alround with corners rounded off and smoothened	Sqr.		166.37	
14	Providing cast iron hand railing as per design alround upper and lower units, fixed into coping slabs including 2 coats of approved paint complete ...	R.ft.		374	
14(*a*)	Do cement concrete do ...	"			
15	Providing a wicket gate as per design for sluice well	L. S.			
	II. Mixing Channel.				
1	Earthwork excavation and using for ramp all round	C.yds.		42	
2	Laying burnt stone jelly concrete in surki mortar with ⅙th cement	C.ft.		784	
2(*a*)	Do quartz jelly do ...	"			
3	Burnt brick in cement mortar (1 : 4) proportion ...	"		250	
4	Cement plastering (1 : 3) ½" thick with corners rounded off complete	Sqr.		12.96	

C. R. IYENGAR,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS

OFFICE OF THE INSPECTOR-GENERAL OF POLICE IN MYSORE, BANGALORE.

Notice No. T. C. 295—37-38, *dated* 19*th November* 1937.

The public are hereby informed that an Avery's Weigh-bridge to weigh motor vehicles is erected in the Office of the Inspector-General of Police in Mysore, Cenotaph Road, Bangalore City, and that motor vehicles brought for weighment will be weighed on payment of a fee of Rs. 10 for each weighment. A certificate of weighment will invariably be issued with each weighment so made.

F. A. HAMILTON,
Inspector-General of Police.